

RECEIVED

Form CP-3
Rev. 6-26-62

40
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-00202-0000

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

NOV 5 1964
11-5-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Burch Exploration, Limited,

Complete Address: 1011 Union Center, Wichita, Kansas.

Lease Name Torluemke Well No. 1

Location CNE-SW Sec. 35 Twp. 2 Rge. (E) (W) 29

County Decatur Total Depth 3895

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas License No. 436

Operation Completed: Hour 11:00AM Day 31 Month 10 Year 1964

The Above well, was plugged as follows:

300' -- 8 5/8" Surface pipe, cement circulated.

3895' -- 4 1/2" Production casing cemented. Well plugged back to 3825'.

Top perforations from 3768' to 3762'.

Sanded well back to 3750', and set 5 Sx. cement with Dump bailer.

Pulled 4 1/2" to 600' and circulated heavy gel mud (25 Sx. gel). Pulled 4 1/2" to 540' and displaced 20 Sx. cement thru 4 1/2". Pulled 4 1/2" to 290' and displaced 20 Sx. cement thru 4 1/2". Pulled 4 1/2", set bridge @35' and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 11/5/64
INV. NO. 115-W