

15-039-20087-00-00

4

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 28 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Halliburton Oil Producing Company,

Complete Address 520 Cameron Building, Oklahoma City, Oklahoma.

Lease Name Mines Well No. A-1

Location SE-SE-NE Sec. 14 Twp. 2 Rge. (E) (W) 30

County Decatur Total Depth 3989'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Murfin Drilling Company,

Address 617 Union National Bldg., Wichita, License No. _____

Operation Completed: Hour 8:00 PM Day 10 Month 5 Year 1969

The above well was plugged as follows:

319'--8 5/8" Surface casing, ce,ent circulated with 225 Sx.
Top of Dakota section @ 1575'.

Circulated hole with heavy mud. Pulled DP to 1800' and displaced 100 Sx. cement thru
DP from 1900' to 1475'. Pulled DP to 300' and displaced 20 Sx. cement thru DP from
300' to 240'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/28/69
INV. NO. 9847-W

Signed: M. L. J. [Signature]
Well Plugging Supervisor