

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-039-20185-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1970
CONSERVATION DIVISION
Wichita, Kansas
10-19-70

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Wichita Plaza, Wichita, Kansas.

Lease Name Mines Well No. 4

Location N/2-N/2-NW Sec. 13 Twp. 2 Rge. (E) (W) 30

County Decatur Total Depth 3960'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling and Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 3:30 PM Day 16 Month 10 Year 1970

The above well was plugged as follows:

255'--8 5/8" Surface casing, cement circulated with 220 Sx.
Top of Dakota section @ 400'.

Circulated hole with heavy mud. Pulled DP to 1675' and displaced 100 Sx. cement thru
DP from 1675' to 1300'. Pulled DP to 280' and displaced 25 Sx. cement thru DP from
280' to 205'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 10-19-70

INV. NO. 2702-W