

KANSAS

24
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

MAR 23 1970
CONSERVATION DIVISION
Wichita, Kansas

15-039-20146-00-00

3-23-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Vickers-KSB&T Building, Wichita, Kansas.

Lease Name Mines Well No. A-3

Location CS/2-NW-SW Sec. 13 Twp. Rge. 2 (E) (W) 30

County Decatur Total Depth 4020'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor B & B Drilling, Incorporated,

Address 207 Petroleum Building, Wichita, Kansas. License No.

Operation Completed: Hour 10:00 AM Day 17 Month 3 Year 1970

The above well was plugged as follows:

330'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1400'.

Circulated hole with heavy mud. Pulled DP to 1640' and displaced 100 Sx. cement thru
DP from 1640' to 1315'. Pulled DP to 345' and displaced 25 Sx. cement thru DP from
345' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 3/23/70
INV. NO. 1624-U