

~~KANSAS~~

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-039-20286-00-00

JUN 17 1974  
6-17-74  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Wilton C. Jackson,

Complete Address 8 North First Street, Nyssa, Oregon.

Lease Name Unger Well No. 1

Location 150' NW of CSE-SE Sec. 25 Twp. 2 Rge. (E) (W) 30

County Decatur Total Depth 3855'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Abercrombie Drilling, Incorporated,

Address 801 Union Center, Wichita, Kansas, License No. \_\_\_\_\_

Operation Completed: Hour 7:45 AM Day 11 Month 6 Year 1974

The above well was plugged as follows:

214'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1275'.

Circulated hole with heavy mud. Pulled DP to 1500' and displaced 110 Cu. Ft. cement  
thru DP from 1500' to 1175'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 6/18/74

INV. NO. 9317-W