

KANSAS

Form CP-3  
Rev. 6-26-62

*Y*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-19029-00-00

RECEIVED  
STATE CORPORATION COMMISSION

FEB 20 1967

2-20-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Specter Pipe and Supply Company.

Complete Address: Box #661, Russell, Kansas.

Lease Name E. H. Unger Well No. 1

Location CNE-SW Sec. 25 Twp. 2 Rge. (E) (W) 30

County Decatur Total Depth 4035

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Lynch Casing Pulling Company,

Address: Route #4, Great Bend, Kansas. License No. 457

Operation Completed: Hour 2:00PM Day 15 Month 2 Year 1967

The Above well was plugged as follows:

227'--8 5/8" Surface pipe, cement circulated with 135 Sx.

3875'--5 1/2" Production casing cemented with 100 Sx. Open hole completion.

Sanded well back to 3860 and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing, found fluid @ 225'. Pushed plug to 450' and ran 5

Sx. cement with dump bailer. Let cement set 16 hours, bailed hole dry

to plug and ran 6 yards Redi-Mix cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Dichel  
Well Plugging Supervisor

DATE 2/20/67

INV. NO. 4789-u