

KANSAS

*pl*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-00199-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 27 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
1-27-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Specter Pipe and Supply, Incorporated,

Complete Address Box #169, Russell, Kansas.

Lease Name Unger Well No. 1

Location CNW-SE Sec. 25 Twp. 2 Rge. (E) (W) 30

County Decatur Total Depth 4340'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Lynch Casing Pulling Company,

Address Great Bend, Kansas. License No. 457

Operation Completed: Hour 12:30 PM Day 25 Month 1 Year 1971

The above well was plugged as follows:

220'--8 5/8" Surface casing, cement circulated with 175 Sx.  
4012'--5 1/2" Production casing cemented on bottom with 125 Sx.. No plug back nor per-  
forations indicated. 5 1/2" had been squeezed from 2350' to 2999' with 200 Sx. cement.  
Sanded well back to 3975' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing  
(1500') and squeezed well initially with 5 sacks hulls and followed with 100 Sx.  
cement from 1625' to 1300' then 27 sacks gel from 1300' to 225' and followed with 25  
Sx. cement from 225 to 150' then 3 sacks gel from 150' to 30' and finally 10 Sx. cement  
from 30' to bottom of cellar. Maximum pump-in pressure-150#. Final shut-in pressure-  
50#. (Mudding and cementing operations performed by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Dikala  
Well Plugging Supervisor

DATE 1/28/71  
INV. NO. 3262-W