

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-30090-00-00

RECEIVED
STATE CORPORATION COMMISSION

JAN 26 1967
1-26-67
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Halliburton Oil Producing Company,

Complete Address: 520 Cameron Building, Oklahoma City, Oklahoma.

Lease Name Jording Well No. A-1

Location 150' West of NW-NE Sec. 23 Twp. 2 Rge. (E) (W) 30

County Decatur Total Depth 4035

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Paine Drilling Company,

Address: Hill City, Kansas. License No. _____

Operation Completed: Hour 1:30 Day 21 Month 1 Year 1967

The Above well was plugged as follows:

299'--7" OD Surface pipe, cement circulated with 160 Sx.

Circulated hole with heavy mud, set plug @ 620' and displaced 15 Sx.

cement thru DP. Heavy mud to 310', set plug with 1/2 sack hulls and dis-

placed 15 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Nichols
Well Plugging Supervisor

DATE 1/26/67
INV. NO. 4660-U