

KANSAS

Y

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20045-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1968
CONSERVATION DIVISION
Wichita, Kansas
5-20-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,

Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name May Well No. 1

Location CNE-SW Sec. 23 Twp. 2 Rge. (E) (W) 30

County Decatur Total Depth 4058

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Paine Drilling Company, Incorporated,

Address: Box "D", Hill City, Kansas. License No.

Operation Completed: Hour 11:00 AM Day 15 Month 5 Year 1968

The Above well was plugged as follows:

297'--7" OD Surface casing, cement circulated with 150 Sx. (6 1/4" Hole).
Top of Dakota section @ 1550'.

Circulated hole with heavy mud. Pulled DP to 1775' and displaced 65 Sx. cement thru
DP. from 1775' to 1450'. Pulled DP to 305' and displaced 15 Sx. cement thru DP from
305' to 245'. Pulled DP, set bridge @ 35' with 1/2 sack hulls and 5 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *A. L. Fichela*
Well Plugging Supervisor

INVOICED

DATE 5/20/68
INV. NO. 7769-W