

15-039-00033-00-01

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,

Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name Mines Well No. 1

Location SE-SE-SW Sec. 11 Twp. 2 Rge. (E) (W) 30

County Decatur Total Depth 4060'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling Company, Incorporated,

Address: Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 6:45 PM Day 11 Month 6 Year 1968

The Above well was plugged as follows:

249'--8 5/8" Surface pipe, cement circulated.
4060'--5 1/2" Production casing cemented on bottom with 150 Sx. (Temperature Survey shows top of cement @ 3436'. No plug back. Top perforations from 3755' to 3759'.
Sanded well back to 3700' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well with 1/4 sacks gel with 5 Sx. hulls and followed with 100 Sx. cement from 1700' to 1380' then 27 sacks gel from 1380' to 270' and followed with 20 Sx. cement from 270' to 210' then 1/4 sacks gel from 210' to 40' and finally 10 Sx. cement from 40' to bottom of cellar. Maximum pump-in pressure--300#. Final shut-in pressure 125'. (Recovered 2500' 5 1/2" casing).

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 6/17/68
INV. NO. 7949-W