

10-6

6 100366

API NUMBER 15- 039-20,833-00-00

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

Approx C NE, SEC. 2, T 2 S, R 30 W/E  
4030 feet from S section line  
1420 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6875

Lease Name Melba Well # 1

Operator: Marmik Oil Co  
Name & Address: 200 N. Jefferson  
El Dorado, Ar. 71730

County Decatur 128.38  
Well Total Depth 3950 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 207

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ U&A x

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Western Kansas Drilling License Number \_\_\_\_\_

Address Hays, Ks. 67601

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Jim Manly

(company name) Western Ks. Drilling (phone) \_\_\_\_\_

were: Spot through drill pipe w/heavy mud between all plugs

1st plug at 2460' w/25 sks

2nd plug at 1775' w/100 sks

3rd' plug at 250' w/40 sks

4th plug at 40' w/wiper plug and 10 sks

Rathole 15 sks Plugging Proposal Received by \_\_\_\_\_ (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None x

Operations Completed: Hour: 2:30PM Day: 6 Month: Oct Year: 19 88

ACTUAL PLUGGING REPORT Hole reported plugged as above

Order 190 sks 60/40 Poz w/6% Gel and 2 sks Celloflake

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 16 1988  
CONSERVATION DIVISION  
Wichita, Kansas

Elevation 2703' D.B. Anhydrite depth 2459' - 92'

Remarks: Did not penetrate Arbuckle Cemented by B.J. Titan  
(If additional description is necessary, use BACK of this form.)

INVOICED / if not observe this plugging.

DATE DEC 19 1988

Signed David K. Wann (TECHNICIAN)

INV. NO. 23404