

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

15-039-20615-00-00

COUNTY Decatur SEC. 2 TWP. 2S RGE. 30W E/W
Location as in quarters or footage from lines:
250' S of C SW NW

Lease Owner K & E Petroleum Corp.
Lease Name WEBER Well No. 1
Office Address 300 Hardage Center, 100 S. Main, Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 10/13/81
Application for plugging filed 10/13/81
Plugging commenced 10/13/81
Plugging completed 10/13/81

Locate Well
correctly on above
Section Platt.

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered.
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Carl Goodrow.
Producing formation _____ Depth to top _____ bottom T.D. 3911'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @ 1380' with 70 sx.
Set 2nd plug @ 390' with 30 sx.
Set 3rd plug @ 40' with 10 sx.
5 sx. in Rathole. 50-50 posmix, 6% gel.

RECEIVED
STATE CORPORATION COMMISSION

State plugger Carl Goodrow.

10-22-1981
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Vice Pres. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of October, 19 81

My Commission expires: 7-13-85

Elizabeth G. Terry
Elizabeth G. Terry Notary Public


CONTRACTORS WELL LOG

15-039-20615-00-00

OPERATOR: K & E Petroleum, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: WEBER #1
 LOCATION: 250' S of C SW NW, Sec. 2-2S-30W
 Decatur County, Kansas
 SPUD DATE: 10/08/81
 COMPLETION DATE: 10/13/81

0	370	Sand & Shale
370	1708	Shale
1708	1983	Sand & Shale
1983	2740	Shale
2740	2830	Shale & Lime
2830	3060	Shale
3060	3290	Lime & Shale
3290	3525	Shale & Lime
3525	3735	Lime & Shale
3735	3911	Lime
	3911	Rotary Total Depth

Spud hole @ 8:45 p.m., 10/08/81. Drilled 370' of a 12 1/4" hole. Ran 9 jts. of 8 5/8" 20# casing set @ 369.79' and cemented with 200 sx. Class A, 2% gel, 3% c.c. Plug was down @ 5:15 a.m., 10/09/81.

3911' TD. Set 1st plug @ 1380' with 70 sx. Set 2nd plug @ 390' with 30 sx. Set 3rd plug @ 40' Solids Bridge with 10 sx. 5 sx. in Rathole. 50-50 posmix, 6% gel. Plug down 8/13/81.

SAMPLE TOPS:

Anhydrite 2416'
 B/Anhydrite 2448'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the WEBER #1, 250' S of C SW NW, Sec. 2-2S-30W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: *Jack L. Partridge*
 Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state, as of this 16th day of October, 1981.

Elizabeth G. Terry
 Elizabeth G. Terry,
 NOTARY PUBLIC

MY COMMISSION EXPIRES 7-13-85

