

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-039-00155-00-00

Decatur County, Sec. 2 Twp. 2S Rge 30W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE NW

Lease Owner M. J. Lebsack

Lease Name Weber Well No. 1

Office Address 502 Kittridge Bldg., Denver, Colorado

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-8-59 19

Application for plugging filed 6-8-59 19

Application for plugging approved 6-8-59 19


Plugging commenced 6-8-59 19

Plugging completed 6-8-59 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius

Producing formation Depth to top Bottom Total Depth of Well 4215 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	240'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug @ 600' w/ 20 sacks cement
2nd plug @ 240' w/ 20 sacks cement
3rd plug @ 40' w/ 10 sacks cement.

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 20 1959
 CONSERVATION DIVISION
 WICHITA, KANSAS

Name of Plugging Contractor Leben Drilling, Inc. (If additional description is necessary, use BACK of this sheet)

Address 905 Central Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Frank Hamlin

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin
905 Central Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of June, 19 59

My commission expires April 23, 1963

Juanita M. Green
Notary Public.



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY


15-039-00155-00-00

Company- M. J. LEBSACK
Farm- Weber No. 1

SEC. 2 T. 2 R. 30W
SE SE NW

Total Depth. 4215'
Comm. 5-30-59 Comp. 6-8-59
Shot or Treated.
Contractor. Leben Drilling, Inc.
Issued. 3-19-60

County Decatur
KANSAS



CASING:
8 5/8" 240' cem. w/160 sx.

Elevation. 2651

Production. Dry

Figures Indicate Bottom of Formations.

clay, sand & shale	240
blue shale	810
shale	1525
shale, sand & lime	1855
anhydrite	1875
lime & shale	3745
lime	3750
lime & shale	3770
lime	4095
shale, lime & chert	4190
Arbuckle	4215RTD
Total Depth	

TOPS: SCOUT	
Heebner	3596
Lansing	3642
Base Kansas City	3870
Marmaton	3881
Cherokee	4011
Cherokee Sand	4105
Cherokee Chert	4132
Arbuckle	4179