


15-039-00033-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Decatur County. Sec. 11 Twp. 28 Rge. 30W (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SE SW
Lease Owner Mugrove Petroleum Corporation, Inc.
Lease Name Mines Well No. 1
Office Address 407 KFH Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 9 19 52
Application for plugging filed April 9 19 52
Application for plugging approved April 9 19 52
Plugging commenced April 9 19 52
Plugging completed April 9 19 52
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4320 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface casing	8-5/8"			8-5/8"	249'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/heavy mud.
Set first plug at 240 feet w/15 sacks cement and 1/2 sack hulls.
Set second plug at 40 feet w/10 sacks cement and 1/2 sack hulls.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mugrove Petroleum Corporation, Inc.
Address 407 KFH Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
GORDON L. KOELLING (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Gordon L. Koelling
407 KFH Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of April, 1952

My commission expires July 9, 1952.

Thay Lou Royer
Notary Public.

24-2675-S 2-52-20M



04-18-1952

15-039-00033-00-00

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: Mines #1
 LOCATION: SE SE SW Section 11-2S-30W
 Decatur County, Kansas
 COMMENCED: March 19, 1952
 COMPLETED: April 9, 1952

0	5	Cellar
5	25	Sand & clay
25	160	Soapstone & sand streaks
160	246	Shale
246	410	Shale & clay
410	2050	Shale
2050	2190	Shale & sand
2190	2235	Anhydrite
2235	2275	Shale & lime streaks
2275	2295	Shale & lime shells
2295	2535	Shale & red bed
2535	2900	Shale & shells
2900	3000	Shale
3000	3145	Shale & lime streaks
3145	3240	Sandy shale
3240	3380	Shale
3380	3801	Shale & lime
3801	3995	Lime
3995	4027	Shale
4027	4284	Lime & shale
4284	4320	Lime
	4320	Rotary Total Depth

Set 249' of 8-5/8" surface casing, cemented with 150 sacks.
 Dry and Abandoned.

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of Mines #1, Section 11-2S-30W, Decatur County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By Gordon L. Koelling
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 17th day of April, 1952.

PLUGGING
 FILE SEC 11 T 2 R 30W
 BOOK PAGE 8 LINE 8

Mary Lou Loun
 Notary Public

My Commission expires July 9, 1952.

04-18-1952
 APR 18 1952