

15-039-20423-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Decatur County. Sec. 10 Twp. 2 Rge. 30  W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines  
NW/4 SE/4 SE/4

Lease Owner D/FW Oil & Gas, Inc.  
Lease Name Wolfram Well No. 1  
Office Address Suite 403 Expressway Towers, 6116 N. Central  
Expressway, Dallas, Texas 75206  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above  
Section Plat

Date Well completed June 23, 1978  
Application for plugging filed (verbally) June 23, 1978  
Application for plugging approved (verbally) June 23, 1978  
Plugging commenced June 23, 1978  
Plugging completed June 23, 1978

Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered  
If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4300  
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Set 1st plug at 1550' with 70 sacks  
2nd plug at 300' with 20 sacks  
3rd plug at 40' with 10 sacks




(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Jack L. Partridge, Ass't. Sec.-Treas. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of June, 1978



Sandra Richman  
Sandra Richman Notary Public.

OPERATOR: D/FW Oil & Gas, Inc.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Wolfram #1  
 LOCATION: NW/4 SE/4 SE/4 Section 10-~~28~~ 30W  
 Decatur County, Kansas  
 SPUD DATE: June 16, 1978  
 COMPLETION DATE: June 23, 1978

0	187	Surface soil, sand & shale
187	335	Shale & sand
335	860	Shale
860	2050	Shale & sand
2050	2333	Shale
2333	2377	Sand
2377	2559	Shale
2559	2591	Anhydrite
2591	2903	Shale & sane
2903	3040	Shale
3040	3957	Shale & lime
3957	3970	Lime
3970	4075	Shale & lime
4075	4300	Lime
	4300	Rotary Total Depth

Spud hole at 9:00 p.m., June 16, 1978. Drilled 330' of 12 1/4" hole. Ran 8 joints of 8-5/8" - 28# surface casing. Set at 329' with 225 sacks of 60/40 posmix, 2% gel, 3% CaCl. Cement did circulate. Plug was down at 3:30 a.m., June 17, 1978.

T.D. 4300'. Set first plug at 1550' with 70 sacks, second plug at 300' with 20 sacks, third plug at 40' with 10 sacks. Plug was down at 8:30 p.m., June 23, 1978. State plugger, Gilbert Balthazor.

SAMPLE TOPS:  
 Anhydrite 2560  
 B/Anhydrite 2591

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 03 1978  
 07-03-1978  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )


Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Wolfram #1, NW/4 SE/4 SE/4 Section 10-~~28~~ 30W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
 Jack L. Partridge,  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 30th day of June, 1978.

Sandra Richman  
 Sandra Richman, Notary Public



My Commission expires July 21, 1979.