


15-039-00199-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Decatur County, Sec. 25 Twp. 2 Rge. 30 (E) (W) X

Location as "NE/CNW/SW" or footage from lines C NW SE

Lease Owner Specter Pipe & Supply, Inc.

Lease Name Unger Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 6-22-62 19\_\_

Application for plugging filed Dec. 30, 1970 19\_\_

Application for plugging approved Dec. 31, 1970 19\_\_

Plugging commenced Jan. 21-1971 19\_\_

Plugging completed Jan. 25, 1971 19\_\_

Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Nichols

Producing formation Kansas City Depth to top 3802 Bottom 4033 Total Depth of Well 4340 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	220 ft.	none
				5 1/2" OD	4012 ft.	1530 feet

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back to 4000 feet. - Dumped 5 sacks cement pumped 5 sacks hulls and 30 sacks mud plus 130 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 8 1971  
CONSERVATION DIVISION  
Wichita, Kansas

2-8-71

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lynch Casing Pulling Company

Address Gt. Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

Specter Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Russell, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 5<sup>th</sup> day of February, 1971

Wilma M. Lindahl

Notary Public.

My commission expires May 21, 1971

15-039-00199-00-00

COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

RAINS & WILLIAMSON OIL CO. &  
Company- H. E. BANGERT, ET AL  
Farm- Unger No. 1

SEC. 25 T. 2 R. 30W  
C NW SE

Total Depth. 4340'  
Comm. 6-12-62 Comp. 6-22-62  
Shot or Treated.  
Contractor. Rains & Williamson Oil Co.  
Issued. 11-3-62

County Decatur  
KANSAS



Elevation. 2793' DE

Production. 139 BOPD, NW

CASING:  
8 5/8" 220' cem w/175 sx.  
5 1/2" 4012' cem w/125 sx.

Figures Indicate Bottom of Formations.

plug & cement	220
shale	1330
shale	1630
shale & sand	2175
shale & lime	2775
shale w/lime streaks	3014
lime & shale	3285
lime & shale breaks	3345
lime	3469
lime & shale	3670
lime	3815
lime & shale	3841
lime	3905
lime w/shale breaks	3965
lime	3978
lime & shale	4064
shale	4123
sandy shale	4250
sandy shale ?	4340 RTD
Total Depth	

TOPS: LOG	
Heebner	3754
Toronto	3788
Lansing	3802
Base Kansas City	4033
Arbuckle	4306

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 4 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
1-4-71