

15-039-20146-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Decatur County, Sec. 13 Twp. 2S Rge. (E) 30 (W)

Location as "NE/CNW/SW" or footage from lines S/2 NW SW
Okmar Oil Company

Lease Owner Okmar Oil Company
Lease Name Mines A Well No. 3

Office Address 1130 Wichita, Plaza - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed 3-17 19 70

Application for plugging filed 3-17 19 70

Application for plugging approved 3-17 19 70

Plugging commenced 7:30 PM 3-17 19 70

Plugging completed 10:00 AM 3-17 19 70

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols - Morland, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4020 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Clay & Sand		0	330	8 5/8"	329	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug @ 1640' w/ 100 sx Plug @ 345' w/ 25 sx - Plug and Bridge
to hold Kelly @ 40' w/10 sx Plugged @ 10:00 AM

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1970
CONSERVATION DIVISION
Wichita, Kansas

3-23-70

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor B & B DRILLING, INC.
Address 207 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Bill Lahar (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Lahar

207 Petroleum Building - Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of March, 19 70

Alma A. Neises

Alma A. Neises

Notary Public.

My commission expires May 31, 1970

B & B DRILLING, INC.

548 Petroleum Building
Wichita, Kansas 67202

March 20, 1970

15-039-20146-00-00

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1970

CONSERVATION DIVISION
Wichita, Kansas

3-23-70

DRILLERS LOG

Re: Mines A #3
S/2 NW SW Section 13-2S-30W
Decatur County, Kansas

OPERATOR: Okmar Oil Company
CONTRACTOR: B & B Drilling, Inc.
COMMENCED: March 9, 1970
COMPLETED: March 17, 1970
TOTAL DEPTH: 4020'

Set 8 5/8" @ 329' w/225 sx

0	180	Clay & Sand	
180	330	Surface	
330	370	Shale	
370	1405	Shale & Sand	
1405	1683	Shale & Lime	
1683	2312	Shale & Lime	
2312	2543	Shale & Sand	
2543	2578	Anhydrite	
2578	2870	Shale	
2870	3050	Shale & Lime	
3050	3200	Shale & Lime	
3200	3490	Lime & Shale	
3490	3817	Shale & Lime	DST #1 3790-3817
3817	3880	Lime	DST #2 3834-3843
3880	4020	Lime	DST #3 3843-3880
4020		Total Depth D & A	DST #4 3948-3960

We certify the above and foregoing to be true and correct copy of the log on the #3 Mines, located in Decatur County, Kansas

B. J. Bohan President

Alma A. Neiser Notary Public

Subscribed and sworn to before me this 20th day
March, 1970. My commission expires May 31, 1970