

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD

K.A.R.-82-3-117

API NUMBER 15-039-20677-00-00
LEASE NAME May Pollnow(Frickey32-2)

TYPE OR PRINT

WELL NUMBER 4-1

NOTICE: Fill out completely 4620 Ft. from S Section Line
and return to Cons. Div. 4620¹⁹⁸⁰ Ft. from E Section Line
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 32 TWP. 2S RGE. 29W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY RAWLINS
PHONE # () 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 2/10/83
Character of Well Oil (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 3/8/02
Plugging Completed 3/8/02

The plugging proposal was approved on 3/8/02 (date)
by Carl Goodrow w/KCC Hays, KS. (KCC District Agent's Name).
Is ACO-1 filed? yes If not, is well log attached? no
Producing Formation LKC Depth to Top 3800 Bottom 3802 TD 4010' Show
depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	250	8 5/8		0
		production	3998	4 1/2	3998	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: Hooked up to 4 1/2" csg. Pumped 180 sxs 60/40 poz 10%gel & 500# hulls. Max Press. 450#. ISIP 100#. Top off w/20sxs & cement at surface. Well has DV tool w/cmt. Circ to surface on annulus. Well P/A. Witnessed and approved by Carl Goodrow w/ KCC

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address
250 N. Water, Suite 300; Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 8 th day of March, 2002

Notary Public - Barbara J. Dodson [Signature]
My Commission Expires: 12/16/03 Form CP-4 Revised 05-88



RECEIVED
APR 01 2002
KCC WICHITA

OK

SWIFT SERVICES, INC.

PO BOX 466

NESS CITY, 67560-0466

COPY

Invoice

DATE	INVOICE #
3/8/02	4203

BILL TO
Murfin Drilling Co. Inc. PO Box 277 Logan, KS 67646

15-039-20677-00-00

TERMS	Well No.	Lease	County	Contractor	Well Type	Well Category	Operator	Job Purpose
Net 30	4-1	May-Pollnow	Decatur		Oil	Abandoned	Lenny	PTA
PRICE REFERE...	DESCRIPTION				QTY	UNIT PRICE	AMOUNT	
575W	Milage				80	2.50	200.00T	
576W-P	Pump Charge				1	500.00	500.00T	
275	Cotton Seed Hulls				5	22.00	110.00T	
329	Swift Ultra Light 60/40 Pozmix (10% gel)				200	5.85	1,170.00T	
581W	Service Charge Cement				200	1.00	200.00T	
583W	Drayage				709.6	0.75	532.20T	
	Subtotal						2,712.20	
	Sales Tax					4.90%	132.90	
	USED FOR				<u>PIA 36</u>			
	APPROVED				<u>ST BK</u>			

RECEIVED
APR 01 2002
KCC WICHITA

Thank you for your business.

Total

\$2,845.10

JOB LOG

SWIFT Services, Inc.


15-039-20677-00-00

DATE 3-8-02 PAGE NO. 1

CUSTOMER *murfin Dr/g* WELL NO. *4-1* LEASE *May-Pollnow* JOB TYPE *P.T.A.* TICKET NO. *4203*

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	<i>0845</i>							<i>on loc</i>
								<i>Hookup To 4 1/2 TD 4000</i>
								<i>D.V. + - 2200 cmt To Surface out 8 5/8</i>
								<i>on 2-Stage Job</i>
								<i>Pump Down 4 1/2 180 SKS 60/40</i>
								<i>10% Gel + 500 # hulls</i>
							<i>450</i>	<i>max PSI 450</i>
			<i>7580⁰</i>					<i>w/ 10 ABC over CS6 vol Pumped shut</i>
								<i>Down well on slow VAC</i>
								<i>let cement set FOR 1HR + Topoff</i>
								<i>Top OFF 4 1/2 w/ 20 SKS 60/40 10% Gel</i>
							<i>100</i>	<i>shut in 4 1/2</i>
								<i>Job Complete</i>
								<i>Down 4 1/2</i>
								<i>200 SKS 60/40 10% Gel</i>
								<i>500 # hulls</i>

RECEIVED
APR 01 2002
KCC WICHITA



CHARGE TO: Murkin Dalg Co.
 ADDRESS: _____
 CITY, STATE, ZIP CODE: Colby KS

TICKET No 4203
 PAGE 1 OF 1

1. SERVICE LOCATIONS <u>Ness City</u>	WELL/PROJECT NO. <u>4-1</u>	LEASE <u>May - Pollnow</u>	COUNTY/PARISH <u>Decatur</u>	STATE <u>KS</u>	CITY	DATE <u>3-8-02</u>	OWNER <u>Same</u>
2.	TICKET TYPE <input checked="" type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR	RIG NAME/NO.	SHIPPED VIA <u>105</u>	DELIVERED TO <u>w. oberlin</u>	ORDER NO.	
3.	WELL TYPE <u>oil</u>	WELL CATEGORY <u>Abandoned</u>	JOB PURPOSE <u>P.T.A.</u>	WELL PERMIT NO.	WELL LOCATION		
4. REFERRAL LOCATION	INVOICE INSTRUCTIONS						

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE	AMOUNT	
		LOC	ACCT	DF		QTY.	U/M	QTY.	U/M			
575		1			MILEAGE	105				2.50	200.00	
576		1			Pump charge				1 EA		500.00	
275		1			Hulls				5 SKS	22.00	110.00	
329					60/40 10% Gel				200 SKS	5.85	1170.00	
581					Bulk Service Charge				200		200.00	
583					Drayage				709.60	T.M.	75	532.20

RECEIVED
 APR 01 2002
 KCC WICKITA

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X J. L. Sumner
 DATE SIGNED 3-8-02 TIME SIGNED 9:00 A.M. P.M.

REMIT PAYMENT TO:

 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	2712.20
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?					
WE UNDERSTOOD AND MET YOUR NEEDS?					
OUR SERVICE WAS PERFORMED WITHOUT DELAY?					
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX	132.90
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL	2845.10
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND					