

15-039-20281-00-00

RECEIVED  
STATE CORPORATION COMMISSION

10-31-74

OCT 31 1974

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
WICHITA, KANSAS 67217

WELL PLUGGING RECORD

Decatur County, Sec. 32 Twp. 2 Rge. 29 (E) (W) X

Location as "NE/CNW/SW" or footage from lines SW NW

Lease Owner Zenith Drilling Co., Inc.

Lease Name May Well No. #1

Office Address Suite 600, 200 West Douglas Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 10-7-74 19


Plugging commenced 10-23-74 19

Plugging completed 10-28-74 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation Depth to top Bottom Total Depth of Well 3980' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"	3976'	1619.61'
				8 5/8"	220'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3700'. Mixed and ran 4 sacks cement thru dump bailer. Squeezed hole with 5 sacks hulls - 14 sacks gel. 110 cu. ft. cement and 23 sacks gel. Released plug 30 cu. ft. cement and 3 sacks gel. Displaced with 10 cu. ft. cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.  
Address Box 364 Great Bend, Kansas


STATE OF Kansas COUNTY OF Barton, ss.

Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer, Jr.  
Box 364 Great Bend, Kansas  
(Address)

Subscribed and sworn to before me this 30 day of October, 1974

Sidney D. Miller  
Notary Public.



My commission expires 24 October 1976