

15-039-20703-00-00

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Decatur SEC. 35 TWP. 2S RGE. 29 E/W  
 Location as in quarters or footage from lines:  
C SE $\frac{1}{4}$ NW $\frac{1}{4}$ , 1980' FNL, 1980' FWL


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Basic Earth Science Systems, Inc.  
 Lease Name Torluemke Well No. 22-35  
 Office Address P. O. Box 3088, Englewood, CO 80155  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed 10/7/83  
 Application for plugging filed Verbal between Toolpusher/Dist. 6 office  
 Plugging commenced 10/7/83  
 Plugging completed 10/7/83

Reason for abandonment of well or producing formation All possible productive zones were condemned by DST's or electric log calculations.

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow (913)674-5593  
 Producing formation Lansing "F" Depth to top 3041 bottom 3046 T.D. 3915

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
St. Corral Anhydrite		2403'				
Topeka Ls.		3537'				
Toronto Ls.		3686'				
Lansing Ls.		3696'				
Base of "G" Zone		3888'				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug #1	2450'	255 Sx. 50/50 poz w/6% gel, 3% CaCl <sub>2</sub>				
Plug #2	1600'	100 Sx. 1.53 ft <sup>3</sup> /Sx.				
Plug #3	300'	40 Sx. 13.3 ppg				
Pour 1 Sx. lime & 1 Sx. cottonseed hulls into csg. Place 8-5/8" wiper plug in surf. pipe and push to 40' w/kelly						
Plug #4	40'	10 Sx.				
Final		10 Sx. in rathole				

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Howco

STATE OF Colorado COUNTY OF Arapahoe, ss.  
Jeffery E. Jones, Vice President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jeffery E. Jones  
P. O. Box 3088, Englewood, CO. 80155  
 (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of October, 1983

My Commission expires: October 21, 1984

RECEIVED  
 STATE CORPORATION COMMISSION  
 11a J. Beardsley  
 Notary Public.  
 OCT 20 1983  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 1620-83