

15-039-20751-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Decatur SEC. 33 TWP. 2 S RGE. 29 E/W
 Location as in quarters or footage from lines:
4520 fsl 4620 fel of section

x			

Locate Well
 correctly on above
 Section Platt.

Lease Owner S & W Drilling Co.
 Lease Name Scott Well No. 33-4
 Office Address P. O. Box 132 Oberlin, Ks. 67749
 Character of Well (Completed as Oil, Gas or Dry Hole): dry hole
 Date Well Completed 11-17-84
 Application for plugging filed 11-20-84
 Plugging commenced 10:30 AM 11-17-84
 Plugging completed 4:30 PM 11-17-84
 Reason for abandonment of well or producing formation Rotary dry

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation none Depth to top bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out.
Ogallala	water	0	155	8 5/8	261	0

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from feet
 to feet for each plug set.

cement plugs of 50/50 Poz 6% gel 3%CC were used as follows
at 2520 circulated hole with mud then spotted 30 sack plug
at 1750 circulated hole with mud then spotted 100 sack plug with 1 sack flocele
at 270 circulated hole with mud then spotted 50 sack plug
pushed solid 8 5/8" plug with 1sack hulls and 1 sack lime to 40' then covered with
10 sacks cement, finished job with 10 sacks cement in rathole

RECEIVED
 STATE CORPORATION COMMISSION

DEC 10 1984

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Co.

STATE OF COUNTY OF , ss. 12-10-84

 (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James L Reed
Oberlin, Ks
 (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of December, 1984

Phelan B Hall
 Notary Public.

My Commission expires: 12-22-86