

15-039-00196-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
11 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Decatur County. Sec. 3 Twp. 2S Rge. (E) 29 (W)

Location as "NE/CNW%SW%" or footage from lines SE NE
Lease Owner Graybol Oil Corporation
Lease Name Castle Well No. 1
Office Address 2200 N. B. T. Bldg., Tulsa 3, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 8 19 63
Application for plugging filed July 8 19 63
Application for plugging approved July 8 19 63
Plugging commenced July 9 19 63
Plugging completed July 9 19 63
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Morland, Kansas
Producing formation None Depth to top Bottom Total Depth of Well 4377 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Severy Sand	Water	3596	3608	8 5/8"	356'	None
Topeka Lime	Tight	3618	3659			
Lansing Lime	Tight	3774	4012			
Conglomerate	Water	4208	4232			
Arbuckle	Water	4232	4362			
Reagan	Water	4362	4377			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud-laden fluid. Set plug at 600'. Cemented with 20 sacks of Portland Cement. Set plug at 350'. Placed in one-half sack of hulls. Cemented with 20 sacks of Portland cement. Set plug at 40'. Filled hole with 10 sacks of Portland Cement from 40' to ground level. Plugging completed at 8:00 A.M., July 9, 1963.

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1963
7-12-63
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graybol Oil Corporation
Address 2200 National Bank of Tulsa Building, Tulsa 3, Oklahoma

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
Lyman C. Dennis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lyman C. Dennis
Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of July, 19 63

My commission expires October 8, 1966

Jane Carrigan
Notary Public.

