

7-28

To: 6 020479
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 039-20,834 -00-00
100' W
SE-NE-SW, SEC. 31, T 2 S, R 29 W/E
1650 feet from S section line
3070 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3545
Operator: H W Operating Co.
Name & Address Suite 100 3535 N.W. 58th
Ok City, Ok 73112
405-949-9414

Lease Name L. Pollnow Well # 1-31
County Decatur 129.6f
Well Total Depth 3989 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well Gas Well Input Well SWD Well U&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling License Number 6033
Address Wichita, Ks.

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Rodney Farr

(company name) (phone)

were: Order 220 sks 60/40 Poz 10% Gel 3% Cal Cl 1 sk F.C. and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs with good circulation and no fluid loss.

Plugging Proposal Received by Gilbert Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:45AM Day: 28 Month: Year: 19 88

ACTUAL PLUGGING REPORT Cir Heavy Mud

1st plug at 2560' w/25 sks

2nd plug at 1775' w/100 sks

3rd plug at 280' w/60 sks

4th plug at 40' w/10 sks

15 sks in rathole 10 sks in mousehole

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1988
9-16-88
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Halliburton Cement
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE 9-20-88

INV. NO. 22296

7-28

NOV 15 1988

Signed Gilbert Balthazor (TECHNICIAN)
Gilbert Balthazor