

4-032398

15-039-20596-00-01

E-24,838

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-039-90096-0000

C S2 SE SE /4 SEC. 30, 02, 29 W  
330 feet from S section line  
660 feet from E section line

Operator license# 30606

12/31

Lease: May-Pollnow Well # 1-3

Operator: Murfin Drilling Company, Inc

County: Decatur 131,40

Address: 250 N. Water - Suite #300  
Wichita, Kansas 67202

Well total depth 4043 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 347 feet

Aband. oil well\_\_\_, Gas well\_\_\_, Input well X, SWD\_\_\_, D & A\_\_\_

Plugging contractor: Murfin Drilling Co., Inc. License# 30606  
~~Swift Construction Company~~

Address: Ness City, Kansas 67650

Company to plug at: Hour: P.M. Day: 31 Month: December Year: 1999

Plugging proposal received from: John Turner

Company: Murfin Drilling Company, Inc. Phone: \_\_\_\_\_

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls  
Rig over hole - emergency plug.  
Run tubing to fill up at 3679'.  
Holes in tubing 2687' - 3214'.  
Exempt area.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 12:30 P.M., Day: 31 Month: December, Year: 1999

Actual plugging report: 8 5/8" set at 347'cwc. 4 1/2" set at 4043' w/175 sxs.  
Perfs 3772' - 3817'. Ran tubing to 3679'. Displaced 55 sxs cement blend with 300# hulls.  
Pulled tubing to 2438' and displaced 55 sxs cement blend with 200# hulls. Pulled tubing to  
1159' and circulated with 70 sxs cement blend to surface. Laid down tubing - tied onto  
4 1/2" and squeezed with another 20 sxs cement blend to Max. P.S.I. 300#. Held.  
Squeezed 8 5/8" with 50 sxs cement blend to Max. P.S.I. 300#. Held. Plug complete.

Remarks:

Condition of casing(in hole): GOOD\_\_\_ BAD\_\_\_ Anhy.plug: YES X NO\_\_\_  
Bottom plug(in place): YES\_\_\_, CALC\_\_\_, NO\_\_\_ Dakota plug: YES X, NO\_\_\_  
Plugged through TUBING\_\_\_, CASING\_\_\_ Elevation: \_\_\_\_\_ GL

I did[ ] / did not[ X ] observe the plugging.

Carl Goodrow  
(agent)

INVOICED

DATE 1/19/00

INV. NO. 061139

Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION

JAN 19 2000  
1-19-2000  
CONSERVATION DIVISION  
Wichita, Kansas

(Handwritten mark)