

6030627

15-039-20030-00-00

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- _____

SE NW, SEC. 23, T 2 S, R 30 W

3300 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988

Lease Name JORDING Well # 3

Operator: HALLIBURTON OIL PRODUCING CO.

County DECATUR 132.34

Name & Address 2915 CLASSEN BLVD.

Well Total Depth 4072' feet

OKLAHOMA CITY, OK.

Conductor Pipe: Size _____ feet

73106

Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE KANSAS

Company to plug at: Hour: PM Day: 27 Month: 12 Year: 19 85

Plugging proposal received from MIKE KELSO

(company name) KELSO CASING. (phone) _____

were: 8 5/8 @ 330' w/225sx. 4 1/2 @ 4069' w/225 PERFS. @ 3835-41'

ORDER COM. CMT. & SAND. RECOVER PIPE. ORDER 120SX. 60/40002 6% GEL 3% CC
40SX. GEL 4SX. HULLS HALLIBURTON CMT. Co. HARVE WATER TRUCKS

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 6:15PM Day: 27 Month: 12 Year: 19 85

ACTUAL PLUGGING REPORT W/BAILER 4SX. CONCMT. ON BOTTOM SAND TO 3775, w/BAILER
SPOT 4SX. COM. CMT. 6N SAND. SHOOT OFF & RECOVERED 1512' OF 4 1/2.

Pump Down 8 5/8 3sx. HULLS & 10SX. GEL 100SX. CMT & 1SX. HULLS
30SX. GEL 80SX. CMT MIX. MAX. PSI 500# CLOSE IN 450# PSI.

PLUG. COMPLETE

RECEIVED STATE CORPORATION COMMISSION

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.

DATE JAN 13 1986

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 11952