

6 050354

10-8-87

039-20,822-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

SW NE NE, SEC. 14, T 2 S, R 30 W/E

4290 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Mines Farms Well # 1

Operator: Berexco Inc.

County Decatur 127.40

Name & Address 970 Fourth Financial Center

Well Total Depth 3920 feet

Wichita, Kansas 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 344

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling License Number 6033

Address Wichita, Kansas

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Steve Carlton

(company name) Murfin (phone)

were: Order 190 sks 60/40 Pozmix 6% Gel 3% Cal Cl 1 sk Flocele and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs with

good circulation and no fluid loss.

Elev 2737' Anhy 2491' - 2526' No Arb.

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:00 AM Day: 8 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT

1st plug at 2490' w/25 sks

2nd plug at 1840' w/100 sks 1 sk Flocele

3rd plug at 360' w/40 sks

4th plug at 40' w/ 8 5/8" wiper w/10 sks

15 sks in rat hole

RECEIVED STATE CORPORATION COMMISSION

OCT 16 1987

10-16-87

Remarks: Halliburton (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION Wichita, Kansas

INVOICED

observe this plugging.

DATE 10-19-87

Signed Gilbert P. Leiker

(TECHNICIAN)

Gilbert P. Leiker

INV. NO. 18555

DEC 03 1987

10-08