

6 030750

15-039-20029-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

NWSW NE SEC. 14, T 2 S, R 30 W

3630 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988

Lease Name MINES Well # 2

Operator: HALLIBURTON OIL PROD. CO.

County DECATUR 130.75

Name & Address Box 10

Well Total Depth 4023' feet

STAFFORD, KANSAS

Conductor Pipe: Size _____ feet

67578

Surface Casing: Size 8 5/8 feet 330'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE KANSAS

Company to plug at: Hour: PM Day: 22 Month: 5 Year: 19 86

Plugging proposal received from TOM

(company name) KELSO CASING. (phone) _____

were: 8 5/8 @ 330 w/225 4 1/2 @ 4022 w/225 PBT 3984 PERF 3949-56'

ORDER SAND & com. cmt. SHOOT & PULL PIPE, ORDER 200 SX.

66/35 pol 10 GEL 2 1/2 ECONOLITE 4 SX. HULLS HALLIBURTON SERVICES.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 PM Day: 22 Month: 5 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBT TO 3900 SPOT 4 SX. COM. CMT.

ON SAND w/BAILER. SHOT & RECOVERED 1200' of 4 1/2"

TIE ON TO 8 5/8 MIX & Pump 4 SX. HULLS 400 SX. CMT MIX. Lockup

@ 600# CLOSE IN @ 600# PSI - Plug Comp.

RECEIVED
STATE CORPORATION COMMISSION

JUN 16 1986

6-16-86

16
6-13-86

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

JUN 18 1986

DATE _____

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 14160