

DISTRICT CONSERVATION AGENT'S REPORT

15-039-00168-00-00

R

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 47-18

LOCATION SW SW SW

SEC. 14 TWP. 2 RGE. 30

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Jording

Operator Jones Shelburne+Farmer, Inc. Address Russell, Kans

Field \_\_\_\_\_ County Decatur

Total Depth 4000 Feet.

Plugging Contractor Forbes Casing Pulling & Globe Cementing

Plugging Contractor's License No. 49

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 215' circulated with cement - 5 1/2" 3981' with 75 sax cement behind - perforated at 3941'.

Set 15 sax cement on bottom with dump bailer - started 1515' 5 1/2" - circulated hole with heavy mud (45 sax Gel) - displaced 20 sax cement through 5 1/2" at 700', heavy mud to 200', displaced 20 sax cement through 5 1/2" at 200', heavy mud to 35', set bridge and 10 sax cement to bottom Cellar.

Mudding and cementing by Globe Cementing Co.

Edwin Perry  
District Conservation Agent

Date 9-25-57

RECEIVED  
STATE CORPORATION COMMISSION

SEP 30 1957 9-30-57  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 14 T. 2 R. 30W  
BOOK PAGE 47 LINE 10