

6 030628 15-039-20009-00-00

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- _____

SENESEW SEC. 14, T 2 S, R 30 W E

1650 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988

Lease Name JORDING Well # "B" 2

Operator: HALLIBURTON OIL PRODUCING CO.

County DECATUR 129.68

Name & Address 2915 CLASSEN BLVD.

Well Total Depth 3990' feet

OKLA. CITY, OK.

Conductor Pipe: Size _____ feet

73106

Surface Casing: Size 7" feet 318'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE KANSAS

Company to plug at: Hour: PM Day: 27 Month: 12 Year: 19 85

Plugging proposal received from MIKE KELSO

(company name) KELSO CASING PULLING. (phone) _____

were: 7" @ 318' w/250 SX. 4 1/2" @ 3983 w/125 SX, PERFS. 3851-56 3920-24'

ORDER COM. CNT & SAND RECOVER PIPE ORDER 180 SX, 60/HOPOL 62 GEL 360

40 SX. GEL. 4 SX. HULLS HALLIBURTON CNT. CO. LARUE WATER TRUCK.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 PM Day: 27 Month: 12 Year: 19 85

ACTUAL PLUGGING REPORT w/BAILER 4 SX. COM. CNT. ON BOTTOM DUMB SAND TO 3800'

SPBT w/BAILER 4 SX. COM. CNT. ON SAND. SHOT & RECOVERED 1714' OF 4 1/2" CASING.

MIX. & Pump Down 8 5/8 3 SX HULLS & 18 SX. GEL. 100 SX. CNT. MIX + 1 SX. HULLS

22 SX. GEL. 80 SX. CNT. MIX. MAX. PSI 800* CLOSE IN PSI 300*.

PLUG. COMPLETE

RECEIVED STATE CORPORATION COMMISSION

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 13 1986

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 11953