

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
08-07-1970
AUG 7 1970
CONSERVATION DIVISION
Wichita, Kansas

15-039-20167-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Thunderbird Drilling,

Complete Address Box #18412, Wichita, Kansas.

Lease Name Mines Well No. 1

Location SE-SE-SE Sec. 11 Twp. 2 Rge. (E) (W)30

County Decatur Total Depth 3940'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 6:30 PM Day 3 Month 8 Year 1970

The above well was plugged as follows:

331'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1125'.

Circulated hole with heavy mud. Pulled DP to 1550' and displaced 100 Sx. cement thru
DP from 1550' to 1225'. Pulled DP to 350' and displaced 20 Sx. cement thru DP from
350' to 290'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. S. F. Nichols
Well Plugging Supervisor

DATE 8/7/70
INV. NO. 2344-W