



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-039-00155-00-01

Operator's Full Name John P. Jennings oil & Gas Producer
 Complete Address Suite 309 200 E. 1st St. Wichita Ks.
 Lease Name Weber Well No. 1
 Location SE-SE-NW Sec. 2 Twp. 2 Rge. 30 (W)
 County Decatur Total Depth 3960
 Abandoned Oil Well Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated old well worked over
 Plugging Contractor Verlin Pfeifer Well Svc.
 Address Box 386 Hill City Ks. License No. No license required
 Operation Completed: Hour 1:15 PM Day 14 Month Feb. Year 1975

The above well was plugged as follows:

K.B. Elev 2653 - Dakota top 1300 - 8 5/8 @ 270' cwc 175sx
2 7/8" Tubing used as casing - Rec. 1362'
Perf - 3802-06 - Dumped 1sx cement @ 3800
Pumped down 8 5/8 3sx Halls - 4sx Gel
80sx cement 50/50 pozmix 6% Gel
26.6x. Gel - Released plug -
45 sx cement 50/50 pozmix 6% Gel.
Allied cementing -

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/20/75
INV. NO. 842-W

2-20-75

Signed: Gilbert Balthazar
Well Plugging Supervisor