



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OK-17-1968  
JUN 17 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company.

Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Mines Well No. 1

Location: SE-SE-SW Sec. 11 Twp. 2 Rge. (E)(W) 30

County: Decatur Total Depth 4060' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Unruh was instructed to plug the well as follows:

249'--8 5/8" Surface pipe, cement circulated.  
4060'--5 1/2" Production casing cemented on bottom with 150 Sx. Top of cement @ 3436' (Temperature Survey). No Plug back. Top perforations from 3755' to 3759'.

Sand well back to 3700' and set 5 Sx. cement with dumbo bailer. Pull 5 1/2" casing, Squeeze well with 35 Sx. gel plus 5 sacks hulls and 130 Sx. cement staged.

Very truly yours,

W. L. Nichols  
Conservation Division Agent