

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

RECEIVED
STATE CORPORATION COMMISSION
NOV 01 1977
11-1-77
CONSERVATION DIVISION
Wichita, Kansas

API Number 15 - 039-20365-00-00 (of this well)
Lease Owner Bolyard Oil & Gas, Ltd.
Address Brooks Towers, 1020 15th Street, Suite 20C, Denver, Colorado 80202
Lease (Farm Name) Torluecke Well No. 1
Well Location C NW SW Sec. 35 Twp. 2 S Rge. (E) 29 (W)
County Decatur Total Depth 3900 Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin October 23, 1977, 7:00 p.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

William Craig Address 702 S. 2nd, Hill City, Ks. 67642

Plugging Contractor Abercrombie Drilling, Inc. License No. _____

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Bolyard Oil & Gas, Ltd.

Address Brooks Towers, 1020 15th Street, Suite 20C, Denver, Colorado 80202

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge
Applicant or Acting Agent
Jack L. Partridge, Ass't. Sec.-Treas.
Date: October 31, 1977

CONTRACTOR'S WELL LOG

OPERATOR: Bolyard Oil & Gas, Ltd.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Torluemke #1
 LOCATION: C NW SW Section 35-2S-29W
 Decatur County, Kansas
 SPUD DATE: October 17, 1977
 COMPLETION DATE: October 23, 1977

0	260	Surface soil, sand & shale
260	800	Shale
800	2115	Shale & sand
2115	2385	Shale
2385	2420	Anhydrite
2420	3112	Shale
3112	3362	Lime & shale
3362	3580	Shale & lime
3580	3790	Lime & shale
3790	3810	Lime
3810	3866	Shale & lime
3866	3900	Shale
	3900	Rotary Total Depth

Spud hole at 5:45 p.m., October 17, 1977. Drilled 260' of 12 1/4" hole. Ran 7 joints of 8-5/8" casing, set at 259.84' with 200 sacks common cement, 2% gel, 3% CaCl. Cement did circulate. Plug was down at 12:01 a.m., October 18, 1977. Pipe welded and strapped.

T.D. 3900'. Set 1st plug at 1400' with 70 sacks, 2nd plug at 240' with 20 sacks, 40' solid bridge with 10 sacks. Cement by Halliburton. Cemented with 50/50 posmix, 6% gel. Plug was down at 7:00 p.m., October 23, 1977.

RECEIVED
 CORPORATION COMMISSION

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

NOV 01 1977
 11-1-77
 CORPORATION DIVISION
 Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Torluemke #1, C NW SW Section 35-2S-29W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

By Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state of this 31st day of October, 1977.

My commission expires July 21, 1979

Sandra Richman
 Sandra Richman, Notary Public



State of Kansas



15-039-20365-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

October 26, 1977

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Torluenke
Description	C NW SW Sec. 35-2-29W
County	Decatur
Total Depth	3900
Plugging Contractor	Abercrombie Drilling, Inc.


Bolyard Oil & Gas, Ltd.
1020 15th Street, Suite 20-C
Denver, Colorado 80202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, P.O. Box 9, Route #1, Palco, Kansas 67657
is hereby assigned to supervise the plugging of the above
named well.