

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
500 INSURANCE BUILDING
212 NORTH MARKET
WICHITA 2, KANSAS

Form CP-1

RECEIVED
STATE CORPORATION COMMISSION

WELL PLUGGING APPLICATION FORM
File One Copy

JUL 12 1963

7-12-63

CONSERVATION DIVISION
Wichita, Kansas

15-039-00196-00-00

Lease Owner Graybol Oil Corporation
(Applicant)
Address 2200 National Bank of Tulsa Building, Tulsa 3, Oklahoma

Lease (Farm Name) Castle Well No. 1

Well Location SE NE Sec. 3 Twp. 2S Rge. (E) 29 (W)

County Decatur Field Name (If any) Wildcat

Total Depth 4377' Oil Well Gas Well Input Well SWD Well D & A X

Was well log filed with application? Yes If not, explain:

Date and hour plugging is desired to begin at once

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of the person on the lease in charge of well owner James F. Shipley
Box 326 Address Cleveland, Oklahoma

Plugging Contractor Graybol Oil Corporation License No.

Address 2200 National Bank of Tulsa Building, Tulsa 3, Oklahoma

Invoice covering assessment for plugging this well should be sent to Graybol Oil Corporation

2200 N. B. T. Bldg. Address Tulsa, Oklahoma

and payment will be guaranteed by applicant.

Signed: Lyman C. Dennis
Applicant or Acting Agent
Lyman C. Dennis

Date: July 10, 1963

GRAYBOL OIL CORPORATION

Decatur County, Kansas

No. 1 Castle

SE NE Section 3-2S-29W

Contractor: Company Tools

Elev: 2806' D.F. 2800' G.L.

Commenced: June 29, 1963

Completed: July 8, 1963

Production: Dry & Abandoned

15-039-00196-00-00

CASING RECORD

Set 8 5/8" Casing at 356' with 290 sacks of cement.

| <u>DEPTH</u> | <u>FORMATION</u> | <u>WELEX ELECTRIC LOG TOPS:</u> | |
|--------------|-----------------------|---------------------------------|------|
| 0-130 | Clay | Niobrara | 620 |
| 130-280 | Water Sand | Greenhorn | 1310 |
| 280-330 | Clay | Dakota | 1435 |
| 330-685 | Shale | Morrison | 2024 |
| 685-1735 | Shale and Sand | Permian | 2254 |
| 1735-1920 | Shale and Anhydrite | Stone Corral | 2517 |
| 1920-1982 | Sand | Severy | 3596 |
| 1982-2250 | Shale and Sand | Topeka | 3618 |
| 2250-2521 | Shale and Lime | Oread | 3719 |
| 2521-2550 | Anhydrite | Lansing | 3774 |
| 2550-2973 | Shale and Shells | Base of Kansas City | 4012 |
| 2973-3083 | Shale and Lime | Fort Scott | 4094 |
| 3083-3380 | Lime and Shale | Basal Penn. Conglomerate | 4208 |
| 3380-3464 | Shale and Lime | Arbuckle | 4232 |
| 3464-3663 | Lime and Shale | Reagan | 4362 |
| 3663-3758 | Lime | Welex Total Depth | 4377 |
| 3758-3810 | Lime and Shale | | |
| 3810-3937 | Lime | | |
| 3937-4070 | Lime and Shale | | |
| 4070-4142 | Shale and Lime | | |
| 4142-4254 | Shale, Lime, and Sand | | |
| 4254-4344 | Lime, Shale and Sand | | |
| 4344-4375 | Lime and Limy Sand | | |
| 4375 | Driller's Total Depth | | |

RECEIVED
STATE CORPORATION COMMISSION

JUL 12 1963
7-12-63

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above is a true and correct log of the above-captioned well as taken directly from the daily drilling reports.

GRAYBOL OIL CORPORATION

By: Lyman C. Dennis
Lyman C. Dennis, Geologist

STATE OF OKLAHOMA

COUNTY OF TULSA

Subscribed and sworn to this 10th day of July, 1963.

My commission expires: October 8, 1966

Paul Carrigan
NOTARY PUBLIC

State of Kansas



15-039-00196-00-00

FORM - CP-8
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
300 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

July 9, 1963

WELL PLUGGING AUTHORITY

Well No. 1
Lease Castle
Description SE NE 3-2-29W
County Decatur

Graybol Oil Corporation
2200 National Bank of Tulsa Building
Tulsa, Oklahoma

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Very truly yours,

A handwritten signature in cursive script, reading "J. P. Roberts".

J. P. ROBERTS
Assistant Petroleum Conservation
Director

Mr. W. L. Nichols Morland, Kansas
is hereby assigned to supervise the plugging of the above
named well.