

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Apollo Energies, Inc.
Address: 10378 N 281 HWY
Phone: (620) 672-9001 Operator License #: 30481
Type of Well: Oil Docket #: NA
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: June 24, 2004 ²⁹ KCC BEM 7/15/04 (Date)
by: Mike Maier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 4522 Bottom: 4542 T.D. 4542
Lansing/Kansas City Depth to Top: 4151 Bottom: 4162 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-135-30,184-00-00
Lease Name: Norton
Well Number: 1-18
Spot Location (QQQQ): _____ - C - NE - NW
660 Feet from North / South Section Line
1980 Feet from East / West Section Line
Sec. 18 Twp. 16 S. R. 26 East West
County: Ness 2124/1966 KCC
Date Well Completed: December, 1965 BEM 7-15-04
Plugging Commenced: June 25, 2004
Plugging Completed: June 25, 2004

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippian	Oil (4522-4545)	0	258'	9 5/8"	258'	0
Lansing/Kansas City	Oil (4151-4162)	0	4525'	7"	4525'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
Spot 50 sxs 60/40 poz 6% gel at 2100' through 2 3/8" tubing, Pull tubing to 1300' spot 50 sxs common with 3% cc, 100 #s hulls;
Pull tubing out of hole, Perforate at 1200' with 2 shots, Pump 80 sxs 60/40 poz 6% gel, 100# hulls, 140 sxs 60/40 poz 6% gel, max press 600#,
down 7" casing, slight vac at shut in. Pumped 100 sxs 60/40 poz 6% gel down 9 5/8" x 7" annulus, max pressure at 250#, shut in at 50#.
Pumped 50 sxs 60/40 poz 6 % gel down 7", hole staying full. Plugging complete at 5:00 p.m (top of rod fish at 2185', tubing fish at 2603')

Name of Plugging Contractor: Cheyenne Well Service, Inc License #: 6454
Address: P.O. Box 384, Ness City, Kansas 67560

RECEIVED
JUL 15 2004
KCC WICHITA

Name of Party Responsible for Plugging Fees: Apollo Energies, Inc
State of Pratt County, Kansas, ss.

Scott Alberg (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____
(Address) 10378 N. 281 HWY, Pratt, Kansas 67124

SUBSCRIBED and SWORN TO before me this 14 day of July, 2004
Nancy E. Harrel My Commission Expires: December 17, 2006
Notary Public

NANCY E. HARREL
Notary Public - State of Kansas
My Appt. Expires Dec 17 2006

KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

BEM