

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

145-00747-00-00

Lease Operator: American Warrior, Inc.

API Number: 15 - spud 6/23/1961

Address: P.O. Box 399

Lease Name: Harms

Phone: (785) 398-2270 Operator License #: 4058

Well Number: 2

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (QQQQ): SW - NW - -

The plugging proposal was approved on: 7/8/04 (Date)

1980 Feet from [X] North / [ ] South Section Line

by: Steve Durant (KCC District Agent's Name)

660 Feet from [ ] East / [X] West Section Line

Is ACO-1 filed? [X] Yes [ ] No If not, is well log attached? [ ] Yes [X] No

Sec. 23 Twp. 20 S. R. 19 [ ] East [X] West

Producing Formation(s): List All (If needed attach another sheet)

County: Pawnee

Cherokee Depth to Top: 4198 Bottom: 4238 T.D. 4290'

Date Well Completed: 7/19/1961

Depth to Top: Bottom: T.D.

Plugging Commenced: 7/8/04

Depth to Top: Bottom: T.D.

Plugging Completed: 7/8/04

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Cherokee oil/water and casing records.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Tubing was stuck in hole below 3500', shot tubing off @ 3500' and recovered 3500'. Set CIBP @ 3000', pressure test casing to 500 psi, lost 150 psi in 10 minutes. Run tubing and packer to 1327' and test casing, casing good from 1327 to surface, take injection rate down tubing, 1 bpm @ 1150 psi, Perforate 2 holes @ 550', spot 35 sacks of common with 3% cc @ 1327, mix 110 sacks of 60/40 poz 6% gel and pump down casing & held 300 psi, pump 10 sacks down 8 5/8 and held 600 psi, job complete.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382

RECEIVED

Address: N. Highway 283, Ness City, KS 67560

JUL 14 2004

Name of Party Responsible for Plugging Fees: American Warrior, Inc.

KCC WICHITA

State of Kansas County, Ness, ss.

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature] (Address) 210 Avenue A, Bazine, KS 67516

SUBSCRIBED and SWORN TO before me this 9th day of July, 20 04

Bernice Moore My Commission Expires: 2/7/06 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

