

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: Noble Energy, Inc.
 Address: 100 Glenborough Dr., #100, Houston, TX, 77067
 Phone: (281) 872-3100 Operator License #: 33190
 Type of Well: D&A Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 5/3/2004 (Date)
 by: Jacob Pfeifer (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Not Present Depth to Top: _____ Bottom: _____ T.D. 1728'
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 023-20551-00-00
 Lease Name: Zimelman
 Well Number: 42-31
 Spot Location (QQQQ): S - E - N - E
1980 Feet from North / South Section Line
650 Feet from East / West Section Line
 Sec. 31 Twp. 3 S. R. 41 East West
 County: Cheyenne
 Date Well Completed: 5/3/2004
 Plugging Commenced: 5/3/2004
 Plugging Completed: 5/3/2004

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Not Present				17# 7"	337' Set @ 343'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well with 60/40 Poz. Mix Cement with 6% Gel & 1/4 Flo-Cele as follows: Plug #1: 50 sx Cement from 1495' - 1220' (275'), Plug #2: 40 sx Cement from 450' - 240' (210'), and Plug #3: 10 sx Cement from 45' - 5' with wiper plug.

RECEIVED

Name of Plugging Contractor: Excell Drilling Company License #: 8273
 Address: P.O. Box 305, Wray, CO 80758-0305

JUN 14 2004

KCC WICHITA

Name of Party Responsible for Plugging Fees: Noble Energy, Inc.

State of Texas County, Harris, ss.

Janis L. Vercher, Sr. Regulatory Specialist (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

(Address) 100 Glenborough Dr., #100, Houston, TX, 77067


SUBSCRIBED and SWORN TO before me this 11th day of June, 20 04

Tina McCoy
Notary Public

My Commission Expires: 9.15.05

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas





CEMENTER'S WELL SERVICE, INC.
 P.O. BOX 336220 • GREELEY, CO. 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE
183918

Date	05-03-04	Well Owner	Noble Energy Inc.	Well No.	42-31	Lease	Zimbelman
County	Cheyenne	State	Kansas			Field	
Charge to	Ex call Drilling Company					Charge Code	
Address	R-#2					For Office Use Only	
City, State	Wray, Colorado, 80758						
Pump Truck No.	1206	Code		Bulk Truck No.	1217	Code	
Type of Job		Depth		Ft.		To	
Surface		Bottom of Surface		Ft.		To	
Plug	3 1/2" D.P.	Plug Landed @		Ft.	Time On	05:00	
Production		Pipe Landed @		Ft.	Time Off	08:15	

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Near				
	Poz. Mix 60/40	100	slcs		
	Calcium Chloride				
	Gel 6 % Flo-Cele 1/4 #Per Sack				
	Handling Charge				
	Hauling Charge				
	Additional Cement				
	1st plug @ 1494' w/ 50 slcs				
	2nd plug @ 310' 1/2 in out of surface casing w/ 40 slcs				
	3rd plug @ 40' w/ 10 slcs, wipe plug				
	Mixing Rate 4 BPM - Displacement Rate 6 BPM				
	Slurry Vol. 1.18 CU. FT/sk-				

RECEIVED
 JUN 11 2004
 KCC WICHITA

Remarks:	Tax Reference Code	Sub Total
	Ks. 4.9 %	Tax
	Disc.	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1206	Pump Truck			60		Kansas 20	
1217	Bulk Truck			60		20	

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Loan, Randy, Luce Received By Tom G. Jones
 Customer or His Agent