



15-039-20185-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 19 1970

CONSERVATION DIVISION  
Wichita, Kansas

10-19-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Vernon Zorn of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Zorn guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Wichita Plaza, Wichita, Kansas.

Lease Name: Mines Well No. 4

Location: N/2-N/2-NW Sec. 13 Twp. 2 Rge. (E)(W) 30

County: Decatur Total Depth 3960' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Zorn was instructed to plug the well as follows:

255'--8 5/8" Surface casing cement circulated with 220 Sx.  
Top of Dakota section @ 1400'.

Circulate hole with heavy mud. Pull DP to 1675' and displace 100 Sx.  
cement thru DP. Pull DP to 280' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent