



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent) STATE CORPORATION COMMISSION

RECEIVED
MAR 23 1970
CONSERVATION DIVISION
Wichita, Kansas

3-23-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. John Armbruster of B & B Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Armbruster guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Mines Well No. A-3

Location: CS/2-NW-SW Sec. 13 Twp. 2 Rge. (E)(W)30

County: Decatur Total Depth 4020' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Armbruster was instructed to plug the well as follows:

330'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1400'.

Circulate hole with heavy mud. Pull DP to 1640' and displace 100 Sx.
cement thru DP. Pull DP to 345' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent