

State of Kansas



15-039-19029-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

FEB 20 1967

2-20-67

Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Ralph Lynch of Lynch Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lynch guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe and Supply Company,

Complete Address: Box # 661, Russell, Kansas.

Lease Name: F. H. Unger Well No. 1

Location: CNE-SW Sec. 25 Twp. 2 Rge. (E)(W)30

County Decatur Total Depth 4035 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Lynch was instructed to plug the well as follows:

227'--8 5/8" Surface pipe, cement circulated with 135 Sx.  
3875'--5 1/2" Production casing cemented with 100 Sx. Open hole completion.

Sand well back to 3860' and set 5 Sx. cement with dump bailer.  
Pull 5 1/2" casing, check fluid in hole, if below 450' set rock bridge @ 450' and 6 yards Redi-Mix cement to bottom of cellar.  
If fluid above 450' set over-night bridge with 5 Sx. quick-set cement. Bail hole and run 6 yards Redi-Mix cement.

Very truly yours,

Conservation Division Agent