



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1971
CONSERVATION DIVISION
Wichita, Kansas
1-27-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Lynch of Lynch Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Lynch guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply, Incorporated,

Complete Address: Box #169, Russell, Kansas.

Lease Name: Unger Well No. 1

Location: CNW-SE Sec. 25 Twp. 2 Rge. (E)(W) 30

County: Decatur Total Depth 4340' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lynch was instructed to plug the well as follows:

220'--8 5/8" Surface casing, cement circulated with 175 Sx.
4012'--5 1/2" Production casing cemented on bottom with 125 Sx. No plug back nor perforations indicated. 5 1/2" has been squeezed from 2999' to 2350' with 200 Sx. cement.

Sand well back to 3975' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 135 Sx. cement and 30 sacks gel, staged.

Very truly yours,

K. L. Nichols
Conservation Division Agent