

State of Kansas



15-039-20045-00-00

ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 20 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
5-20-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Duane Born of Paine Drlg. Co., Inc., has this date requested permission to plug the following described well:

Mr. Born guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name: May Well No. 1

Location: CNE-SW Sec. 23 Twp. 2 Rge. (E)(W) 30

County: Decatur Total Depth 4058 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Born was instructed to plug the well as follows:

297'--7" OD Surface pipe, cement circulated with 150 Sx. (6 1/4" Hole).  
Top of Dakota section @ 1550'.

Circulate hole with heavy mud. Pull DP to 1775' and displace 65 Sx.  
cement thru DP. Pull DP to 305' and displace 15 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 5 Sx. cement to bottom  
of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent