

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 007-228060000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 3/19/04

Well Operator: Woolsey Operating Company, LLC KCC License #: 33168
(Owner / Company Name) (Operator's)

Address: P.O. Box 168 City: Medicine Lodge

State: Kansas Zip Code: 67104 Contact Phone: (620) 886 - 5606 #27

Lease: Ricke Well #: F-2 Sec. 31 Twp. 33 S. R. 13 East West

Approx - S/2 - N/2 N/2 - NE Spot Location / QQQQ County: Barber

460 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1370 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 10 3/4" Set at: 231 Cemented with: 200 Class "A" Sacks

Production Casing Size: 4 1/2" Set at: 2948 Cemented with: 100 Class "H" Sacks

List (ALL) Perforations and Bridgeplug Sets: Cottonwood 2864' to 2868' w/ 4 SPF

Elevation: 1882' (G.L. / K.B.) T.D.: 5360 PBTD: 2893 Anhydrite Depth: 1560'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Set 4 1/2" CIBP @ 2840' w/ 2 sax cement on top.

Cut casing @ freepoint. Spot 40 sax plug @600', 40 sax @ 250' and 10 sax @ 40' to surface. 60/40 6% gel.

RECEIVED

JUL 13 2004

KCC WICHITA

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? In process

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Carl W. Durr

Woolsey Operating Company, LLC Phone: (620) 886 - 5606 #27

Address: P.O. Box 168 City / State: Medicine Lodge, KS 67104

Plugging Contractor: Clarke Corp. KCC License #: 5105
(Company Name) (Contractor's)

Address: P.O. Box 187, Medicine Lodge, KS 67104 Phone: (620) 886 - 5665

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 7/12/04 Authorized Operator / Agent: Carl W. Durr
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Woolsey Operating Company, LLC
125 N. Market, Suite 1000
Wichita, KS 67202-1775

July 14, 2004

Re: RICKE F #2
API 15-007-22806-00-00
N2NE 31-33S-13W, 460 FNL 1370 FEL
BARBER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely

David P. Williams
Production Supervisor