

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

15-015-19499-00-00

API # 15 - 015-95,336 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date _____.

Well Operator: VESS OIL CORPORATION KCC License #: 5030 6/05
Address: 8100 E. 22nd Street North, Bldg. 300 (Owner / Company Name) City: Wichita (Operator's)

State: KS Zip Code: 67226 Contact Phone: (316) 682 - 1537 X103

Lease: Burlingame Stokes A Well #: 38 Sec. 28 Twp. 25S S. R. 05E East West

App. 120' SE - SE - SW Spot Location / QQQQ County: Butler

450' Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2345' Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 10-3/4 Set at: 50' Cemented with: 35 Sacks

Production Casing Size: 7 Set at: 2464' Cemented with: 160 Sacks

List (ALL) Perforations and Bridgeplug Sets: Arbuckle OH 2471-74, CIBP-2100', KC 1988-98, 1970-78, Lansing 1716-21,
1696-1700, 1670-76

Elevation: 1381/1384 (G.L. / K.B.) T.D.: 2474' P.B.T.D.: 2100' Anhydrite Depth: _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Run tubing to 1970'. Mix and pump 125 sx Class A,
3% cc. Pull tb. wireline tag cement - have at least 1620' top. Perf at 275'. Try to pump 65/35 Pozmix, 4% gel in
if tight, perf above 145' old sqz @ 100', try to circ cmt to surface. If tight land 7" tie onto 10-3/4 nipples try to pump cmt

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Casey Coats

Phone: (316) 682 - 1537 X104

Address: 8100 E. 22nd St., North, Bldg. 300 City / State: Wichita, KS 67226

Plugging Contractor: United Cementing and Acid, Inc. KCC License #: 30437 9/04
(Company Name) (Contractor's)

Address: 2510 W. 6th, El Dorado, KS 67042 Phone: (316) 321 - 4680

Proposed Date and Hour of Plugging (if known?): November 14, 2003 9:00 a.m. 5-11-04 Plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5/7/04 Authorized Operator / Agent: WR Hays (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAY 10 2004
KCC WICHITA