

KANSAS CORPORATION COMMISSION RECEIVED  
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION JUL 01 2004

Please TYPE Form and File ONE Copy

KCC WICHITA

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 009-30289 ~00 ~00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date \_\_\_\_\_

Well Operator: American Warrior Inc. KCC License #: 4058 11/04

Address: P.O. Box 399 (Owner / Company Name) City: Garden City (Operator's)

State: Ks. Zip Code: 67846 Contact Phone: ( 620 ) 272 - 1023

Lease: Kraft-Prusa UT K&S below 11/04 Well #: 8-8 Sec. 13 Twp. 17 S. R. 11  East  West

C - NW - SE - NE Spot Location / QQQQ County: Barton

3630 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

990' Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # NA  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 85/8 Set at: 631' Cemented with: 500 Sacks

Production Casing Size: 41/2 Set at: 3319' Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3102 to 3224, CIBP@ 1255'

Elevation: 1896 ( G.L. /  K.B.) T.D.: 3320 PBTD: 3280 Anhydrite Depth: NA (Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Perf 1250' to 51'4spf and 640' to 41'4spf. Hook up to 41/2 casing, pump cement cir to surface, Shut braiden head in and squeeze with 115sx 60/40 posw/10%gel. Cut casing off 6' below surface, cap, Back fill and replace top soil.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? No files on this well.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Jody Smith

Phone: ( 620 ) 272 - 1023

Address: P.O. Box 399 City / State: Garden City Ks. 67846

Plugging Contractor: Swift Services, Inc. KCC License #: 32382 10/04

Address: P.O. Box 466 Ness City Ks. 67560 Phone: ( 785 ) 789 - 2300 (Contractor's)

Proposed Date and Hour of Plugging (if known?): NA

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 7/1/04 Authorized Operator / Agent:  (Signature)

Mail to: KCC - Conservation Division, 150 S. Market - Room 2078, Wichita, Kansas 67202

# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

American Warrior, Inc.  
PO Box 399  
Garden City, KS 67846

July 13, 2004

Re: KRAFT-PRUSA UT #8-8  
API 15-009-30289-00-00  
NWSENE 13-17S-11W, 1650 FNL 990 FEL  
BARTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #4  
2301 E. 13th  
Hays, KS 67601  
(785) 625-0550

Sincerely



David P. Williams  
Production Supervisor