

RECEIVED  
KCC DISTRICT #2

JUL 13 2004

WICHITA, KS

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-053-00787-00-00 (Identifier number of this well). This must be listed for wells drilled since 1957; if no API# was issued, indicate spud or completion date.

WELL OPERATOR John J. Darrah KCC LICENSE # 5088  
(owner/company name) (operator's)

ADDRESS 225 n. Market #300 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 263-2243

LEASE Rathbun WELL# 2 SEC. 16 T. 17 R. 8W (East/West)

SE - SE - SE - SPOT LOCATION/0000 COUNTY ~~SE~~ ELKSWORTH

330 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENGR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE none SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 282 CEMENTED WITH 125 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 3197 CEMENTED WITH 125 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: OPEN HOLE 3197-3232

ELEVATION 1776 KB T.D. 3232 PFTD \_\_\_\_\_ ANHYDRITE DEPTH est 1180  
(G.L./K.S.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Run tubing to bottom, 25 sk balanced plug, pull tubing to 1125, perf 4.5" w/ tubing gun, pump 50sk balanced plug, pull tubing to 650, perforate, run 50 sk plug, pull tubing to 300

pump 100 sack plug, pump 50 sx between 8 5/8 and 4.5". Top off later.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? no

If not explain why? Drilled 1947

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

G.P. Stoepfelwerth PHONE# (316-943-0383 home  
cell 620-786-4046

ADDRESS ABOVE City/State \_\_\_\_\_

PLUGGING CONTRACTOR Classic Well Service/ Allied Cementing KCC LICENSE # \_\_\_\_\_  
(company name) (contractor's)

ADDRESS Claffin, KS / Russell, KS PHONE # (620) 786-5140

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) ASAP for scheduling

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: July 12, 2004 AUTHORIZED OPERATOR/AGENT: [Signature]  
(signature)

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bldg. Wichita, Kansas

COPY

Company - CITIES SERVICE OIL COMPANY  
Farm - Rathbun No. 2

SEC. 16 T. 17 R. 8W  
SEc SE  
330' N & 330' W of SE corner

Total Depth. 3332'

County. Ellsworth  
KANSAS


Comm. 8-12-47

Comp. 9-11-47

Shot or Treated. Acid. w/1000 gals. 9-6-47; 1500 gals. 9-12-47.

Contractor. R. W. Rino Drilling Co.

Issued. 12-27-47



CASINGS:

8-5/8" 282' Cem. w/125 sx  
4-1/2" 3197' Cem. w/125 sx

Elevation. 1725 Gr.

Production. Phy. Pot. 444 BO,  
no water, 24 hours.

Figures indicate bottom of Formations

shale & shells	0-955
salt	1105
shells, shale & red bed	1180
shale & shells	1330
shale & lime sdy	1550
lime brkn	1686
lime & shale	2581
lime	2705
lime & shale	3025
lime	3101
lime & shale	3206
3206 RTD-3199 SLM	
lime	3352
Total Depth	

Tops:

Lansing corr.	2832
Arbuckle corr.	3196
penetration	56

Pillup:

50' oil in 5 mins. at 3199.  
100' oil in 3 hrs. 5 mins. at 3199.  
250' oil in 4 hrs. at 3200.  
375' oil in 7 1/2 hrs. at 3204.  
1000' oil in 12 hrs. at 3208.  
1200' oil in 14 hrs. at 3211.  
1450' oil in 15 hrs. at 3211.

Sept. 10 and 11, 1947-Deepened 3211-32.

K. G. S. LIBRARY

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Darrah, John Jay, Jr.  
225 North Market, Ste 300  
Wichita, KS 67202-3408

July 14, 2004

Re: RATHBUN #2  
API 15-053-00787-00-00  
SESESE 16-17S-8W, 330 FSL 330 FEL  
ELLSWORTH COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #2  
130 S. Market, Room 2125  
Wichita, KS 67202-3208  
(316) 337-6231

Sincerely  


David P. Williams  
Production Supervisor