

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
Wichita, Kansas 67217

Rev. 3-15-72
FORM CP-1

RECEIVED
STATE CORPORATION COMMISSION
JUN 13 1974
6-13-74
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING APPLICATION FORM
File One Copy

15-039-20286-00-00

Lease Owner Wilton C. Jackson
Address 8 North First Street, Myssa, Oregon 97913
Lease (Farm Name) UNGER Well No. #1
Well Location 150' NW C SE SE Sec. 25 Twp. 2S Rge. ~~XXX~~ 30 (W)
County Decatur Total Depth 3855' Field Name Unknown
Oil Well Gas Well Input Well SWD Well Rotary D & A X
Well Log filed with application as required Yes
Date and hour plugging is desired to begin 7:45 a.m., June 11, 1974

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Mr. Joe Weber Address Great Bend, Kansas

Plugging Contractor Abercrombie Drilling, Inc. License No.

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Wilton C. Jackson

Address 8 North First Street, Myssa, Oregon 97913

and payment will be guaranteed by applicant or acting agent.

Signed: Jerry A. Langrehr
Applicant or Acting Agent
Jerry A. Langrehr, Vice President
Date: June 12, 1974

15-039-20286-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	Wilton C. Jackson
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	UNGER #1
LOCATION:	150' NW C SE SE Sec. 25-2S-30W Decatur County, Kansas
GEOLOGIST:	George Waite
SPUD DATE:	June 5, 1974
COMPLETION DATE:	June 11, 1974

0	220	Clay, Sand and Rock
220	1745	Shale
1745	2044	Sand
2044	2162	Shale
2162	2449	Shale and Lime
2449	2541	Shale
2541	2575	Anhydrite
2575	3060	Shale
3060	3190	Shale and Lime
3190	3805	Lime and Shale
3805	3855	Lime
	3855	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1974
CONSERVATION DIVISION
Wichita, Kansas
6-13-74

Drilled 224' of 12½" hole. Set 5 jts. of 8 5/8" surface casing @ 222' K.B. Cemented with 160 sacks of 60/40 Posmix with 3% HA5. Cement circulated. Plug was down @ 5:00 p.m. June 5, 1974. D & A: 1st Plug set @ 1500' with 110 cu. ft. cement, 2nd Plug set @ 215' with 30 cu. ft. cement, 3rd Plug set @ 40' with 10 cu. ft. cement. Plug was down @ 7:45 a.m., June 11, 1974. State Plugger: Bill Nichols.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jerry A. Langrehr, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the UNGER #1, 150' NW C SE SE, Section 25-2S-30W, Decatur County, Kansas


ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
Jerry A. Langrehr
Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 12th day of June 1974.

Nancy E. Bledsoe
Nancy E. Bledsoe - Notary Public

My Commission Expires: April 8, 1978





15-039-20286-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

June 17, 1974

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Unger
Description	150'NW C SE SE 25-2-30W
County	Decatur
Total Depth	3855'
Plugging Contractor	Abercrombie Drilling, Inc.

Wilton C. Jackson
8 North First Street
Nyssa, Oregon 97913

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,

J. Lewis Brock
J. Lewis Brock, Administrator

Mr. ~~W. L. Nichols, P. O. Box 157, Morland, Kansas 67650~~
is hereby assigned to supervise the plugging of the above named well.