

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
500 INSURANCE BUILDING  
212 NORTH MARKET  
WICHITA 2, KANSAS

Form CP-1

RECEIVED  
STATE CORPORATION COMMISSION

JAN 29 1963

1-29-63  
CONSERVATION DIVISION  
Wichita, Kansas

15-039-00453-0000 WELL PLUGGING APPLICATION FORM  
File One Copy

Lease Owner Halliburton Oil Producing Company  
(Applicant)  
Address 520 Cameron Building, Oklahoma City, Oklahoma

Lease (Farm Name) May Well No. 1

Well Location 150' E/C NW-SW Sec. 23 Twp. 2S Rge. (E) 30 (W)

County Decatur Field Name (If any) Jording

Total Depth 4092 Oil Well  Gas Well  Input Well  SWD Well  D & A xxx

Was well log filed with application? Yes If not, explain:

Date and hour plugging is desired to begin 1-9-63

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of the person on the lease in charge of well owner G.C. Schneider  
Address 520 Cameron Bldg. Okla. City 6, Okla.

Plugging Contractor Burch Drilling Company License No.   
Address 1011 Union Center, Wichita, Kansas

Invoice covering assessment for plugging this well should be sent to Halliburton Oil Prod. Co.  
Address 520 Cameron Bldg., Okla. City 6, Oklahoma

and payment will be guaranteed by applicant.

Signed: D.P. Swearingen  
Applicant or Acting Agent

Date: 1-9-63

15-039-00453-00-00

CONTRACTOR'S  
WELL LOG

Halliburton Oil Producing Co.  
#1 May  
C NW SW Sec. 23-2S-30W  
Decatur County, Kansas

Set 8 5/8" @ 288' with 225 sacks cement.  
Commenced: 12-30-62  
Completed: 1-9-63  
Elevation: 2856 KB

D & A

1965 Shale  
2300 Lime & Shale  
2326 Blaine Anhydrite  
2597 Shale  
2632 Cimarron Anhydrite  
2662 Lime & Shale  
2840 Lime & Sand  
3154 Lime & Shale  
3243 Lime & Sand  
3651 Lime & Shale  
3754 Lime & Sand  
3855 Lime & Shale  
3875 Lime  
4000 Lime & Shale  
4090 Lime

Tops  
Heebner 3796 (-940)  
Lansing 3844 (-988)  
Base Kansas City 4064 (-1208)

DST #1. 3797-3855. Open 40 minutes.  
Recovered 30' mud. IBHP 140#, IFP 10#,  
FFP 20#, FBHP 60#.

DST #2. 3968-4000. Open 1 hour.  
Recovered 2' oil, 12' slightly oil cut  
mud. IBHP 480#, IFP 10#, FFP 20#,  
FBHP 70#.

4090 Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION


JAN 29 1963

1-29-63


CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS            )  
  ) ss.  
COUNTY OF SEDGWICK )

I, Earl M. Burch, General Partner of Burch Exploration, Ltd. being  
duly sworn on oath, state: That I have knowledge of the facts, statements and  
matters herein contained and that the same are true and correct.

  
Earl M. Burch, General Partner

Subscribed and sworn to before me this 24th day of January, 1963.

  
Minnie E. Matson, Notary Public

My commission expires: June 18, 1964



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

January 9, 1963

WELL PLUGGING AUTHORITY

Well No. 1  
Lease May  
Description NW SW 23-2-30W  
County Decatur

Halliburton Oil Producing Co.  
Cameron Bldg.  
2915 Classen Blvd.  
Oklahoma City, Oklahoma

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Very truly yours,

J. P. ROBERTS  
Assistant Petroleum Conservation  
Director

Mr. W. L. Nichols Moreland, Kansas  
is hereby assigned to supervise the plugging of the above  
named well.

