

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
245 North Water  
WICHITA, KANSAS 67202

Rev. 6-3-74  
FORM CP-1

WELL PLUGGING APPLICATION FORM  
File One Copy

API Number 15-039-20481-00-00 (of this well)  
Lease Owner Suburban Propane Gas Corporation  
Address P. O. Box 17689, San Antonio, Texas 78217  
Lease (Farm Name) HELMPKEMP Well No. 1  
Well Location C NW NW SE Sec. 17 Twp. 2S Rge. 30W (E)      (W) X  
County Decatur Total Depth 4350' Field Name       
Oil Well      Gas Well      Input Well      SWD Well      Rotary D & A X  
Well Log attached with this application as required Yes  
Date and hour plugging is desired to begin 12:00 midnight, 03-16-80

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Bill Craig Address 702 So. 2nd Street, Hill City, Ks

Plugging Contractor Abercrombie Drilling, Inc. License No.     

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to

Name Suburban Propane Gas Corporation

Address P. O. Box 17689, San Antonio, Texas 78217

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge  
Applicant or Acting Agent

Jack L. Partridge

Date: March 19, 1980

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 24 1980  
CONSERVATION DIVISION  
Wichita, Kansas  
3-24-80

15-039-20481-00-00

CONTRACTOR'S WELL LOG

OPERATOR: Suburban Propane Gas Corporation  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Helmpkemp #1  
 LOCATION: C NW NW SE, Section 17-2S-30W  
 Decatur County, Kansas  
 SPUD DATE: March 09, 1980  
 COMPLETION DATE: March 16, 1980

0	332	Shale and sand
332	2607	Shale
2607	2630	Anhydrite
2630	2985	Shale
2985	3315	Lime and shale
3315	3475	Shale and lime
3475	3604	Lime and shale
3604	4350	Lime
4350		Rotary Total Depth

Spud hole at 5:00 p.m., March 09, 1980. Drilled 332' of 12 1/4" hole. Ran 8 joints of 8-5/8" - 24# casing. (Talley 324.06'). Set at 331.66' with 265 sacks of Class A cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 11:55 p.m., March 09, 1980.

T.D. 4350'. Set 1st plug at 1600' with 70 sacks, 2nd plug at 330' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks and rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Job was complete at 12:00 midnight, March 16, 1980.

SAMPLE TOPS:  
 Anhydrite 2607'  
 B/Anhydrite 2630'

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 24 1980  
 CONSERVATION DIVISION  
 Wichita, Kansas

324-80


STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the HELMPKEMP #1, C NW NW SE, Section 17-2S-30W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
 Jack L. Partridge  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid as of this 18th day of March, 1980.



Sherrie L. Brooks  
 Sherrie Brooks, Notary Public

My commission expires 08-21-82.

State of Kansas



15-039-20481-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
WILLIAM G. GRAY

Governor  
Chairman  
Commissioner  
Commissioner

Carol J. Larson, Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

March 18, 1980

WELL PLUGGING AUTHORITY

**Subu**

Helmkamp Well no. 1  
NW NW SE, Sec.17-2S-30W  
Decatur County  
4350'  
Abercrombie Drig., Inc.


Suburban Propane Gas Corporation  
Box 17689  
San Antonio, TX 78217

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) day from the above date.

Yours very truly,

  
J. LEWIS BROCK, Administrator

Mr. Gilbert Balthazor, Box 9, Palco, KS 67657

is hereby assigned to supervise the plugging of the above named well