

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
**This Form must be Typed  
Form must be Signed  
All blanks must be Filled**

API # 15 - 159-20152-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date July 1st, 2004.

Well Operator: D. S. & W. Oil Operations KCC License #: 6901  
(Owner / Company Name) (Operator's)  
 Address: P.O. Box 231 City: Claffin  
 State: Kansas Zip Code: 67525 Contact Phone: ( 620 ) 587 - 3361  
 Lease: Rose Bieberle Well #: 2 Sec. 20 Twp. 18 S. R. 10  East  West  
NE - SW - NE - Spot Location / QQQQ County: Rice

*12/04*

\_\_\_\_\_ Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)  
 \_\_\_\_\_ Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks  
 Surface Casing Size: 10-3/4" Set at: 240' Cemented with: 175 Sacks  
 Production Casing Size: 5-1/2" Set at: 3328' Cemented with: 200 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perf: 3262'-63.5'; 3270.5'-71.5'; 3279'-80.5'

Elevation: 1745' ( G.L. /  K.B.) T.D.: 3300' PBTD: 3298' Anhydrite Depth: 486'  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): As Per KCC

**RECEIVED**  
**JUL 15 2004**  
**KCC WICHITA**

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? Not provided by the operator.

**Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.**

List Name of Company Representative authorized to be in charge of plugging operations: Edward S. Nemnich

Phone: ( 620 ) 587 - 3361

Address: P.O. Box 231 City / State: Claffin, Kansas 67525

Plugging Contractor: D. S. & W. Well Servicing, Inc. KCC License #: 6901  
(Company Name) (Contractor's)

Address: P.O. Box 231, Claffin, Kansas 67525 Phone: ( 620 ) 587 - 3361

Proposed Date and Hour of Plugging (if known?): ASAP


Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: July 13th, 2004 Authorized Operator / Agent: Edward S. Nemnich  
(Signature)

*6/05*

**Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202**

10-76 Map No. REPL #1  
OPER R.M. EDWARDS C/O S.A. MARTIN  
BOX 635, GREAT BEND, KS  
WELL #2 BIEBERLE  
CONTR BURT DRLG  
ORTH WEST FIELD (MULTI-PAY)



S-T-R 20-18S-10W  
SPOT NE SW NE  
CO RICE, KS  
ELEV 1745 KB

I.P. CO IPP 10 BOPD + 98% WTR, ARB 3260-80  
API # 15-159-20152  
3290' PTD

KB LOG TOPS  
ANH 486 +1259  
HB 2800 -1055  
BL 2922 -1177  
LAN 2940 -1195  
CGL SD 3260 -1515  
ARB 3270 -1525  
LTD 3298 -1553  
RTD 3300 -1555  
TD IN ARB FORM

SPUD 8-19-68 10 3/4" 146/150 SX GEOL - W. O. JOHNSON  
CORE 1 (LAN) 3192-20, REC 28' NO DESC AVAIL  
DST 1 (LAN) 3126-92, OP 30 MIN, SI 30 MIN, OP 30 MIN, SI  
30 MIN, REC 70' DRLG MUD, SLTLY OIL SPKD, ISIP 740/30  
MIN, IFP 51-77, FFP 64-81, FSIP 697/30 MIN  
CORE 2 (CONG SD-ARB) 3250-3300, REC 50' NO DESC AVAIL  
DST 2 (ARB) 3277-76, OP 30 MIN, SI 30 MIN, OP 30 MIN, SI  
30 MIN, REC 5' OIL + 1680' SOCW, ISIP 974/30 MIN, IFP  
57-521, FFP 508-752, FSIP 967/30 MIN  
DST (STRD) 3 (CONG SD) 3264-68, OP 30 MIN, SI 45 MIN, OP  
30 MIN, SI 45 MIN, REC 10' FREE OIL, + 25' OCM, ISIP  
1059/45 MIN; IFP 13-19, FFP 11-14, FSIP 1033/45 MIN  
RTD 3300 LOG 5 1/2" @ 3299/75 SX

RECEIVED

JUL 15 2004

KCC WICHITA

RECEIVED

JUL 15 2004

KCC WICHITA

MICT CO PERF (ARB) 4/3262-6 $\frac{3}{2}$ , 4/3270 $\frac{1}{2}$ -3271 $\frac{1}{2}$ , 4/3279 $\frac{1}{2}$ -  
3280 $\frac{1}{2}$ , 250/ACID, SWAB LOAD, POP, P 45 BO/24 HRS, PERF ARB  
40/3260-3280, 250/ACID, P 42 BOPD + 82% WTR (GTY 37.7)  
CO IPP 10 BOPD + 98% WTR, ARB 3260-80 COMPLETED 10-8-68  
INFO RELEASED 1-22-70

REPLACES COMP ISSUED 10-11-68

REPLACED TO ADD 3 DSTS & 2 CORES -INFO HAD BEEN TITE

4/3262-6 $\frac{3}{2}$   
4/3270 $\frac{1}{2}$ -3271 $\frac{1}{2}$   
4/3279 $\frac{1}{2}$ -3280 $\frac{1}{2}$

REPL COMP ISSUED 1-29-70

 Petroleum Information

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

D S & W Well Servicing, Inc.  
403 Front Street  
Claflin, KS 67525

July 16, 2004

Re: ROSE BIEBERLE #2  
API 15-159-20152-00-00  
NESWNE 20-18S-10W, 3630 FSL 1650 FEL  
RICE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #2  
130 S. Market, Room 2125  
Wichita, KS 67202-3208  
(316) 337-6231

Sincerely,  


David P. Williams  
Production Supervisor